<section-header><section-header><section-header><section-header><section-header><section-header><text><text><text><text><text><text>

ENGINEE

North Carolina Wetland Mitigation Evaluation Pilot Survey Study Objective and Purpose

- The purpose of this study is to evaluate the ecological integrity of wetland compensatory mitigation projects overall and by each of the three types of NC mitigation methods.
- The study primarily followed the National Wetland Conditional Assessment (NWCA) methodology
- The results of this study will be compared to and synthesized by ELI with the 2011 Ohio Mitigation Pilot Study.

3 types of mitigation – Permittee-Responsibe, Mitigation Bank, and In-Lieu Fee. PG Environmental conducted the Ohio study.

North Carolina Mitigation

. **Permittee-Responsible** – 36,090 Ac Total (21,001 Ac Restoration)

- Private individual/organization 28,702 Ac total
- NC Department of Transportation (DOT) 6,417 Ac total
- Other (e.g. City/Town Government) 972 Ac total

Mitigation Bank – 14,514 Ac total (7,812 Ac restoration)

In-Lieu Fee – 9,972 Ac total (2,952 Ac restoration) Operated by the NC Ecosystem Enhancement Program (EEP), a non-regulatory division of NC DENR.

Data as of beginning of project, September 2011. In the 1990s most NC compensatory mitigation was "permittee responsible" – 50% failure rate. So in 1997 state legislation founded the "Wetlands Restoration Program – run under DENR – wetland oriented mitigation program – this gave permittees an alternative mitigation option. In 1999, DOT started using WRP for some of their rapidly growing mitigation needs, but the situation was not working appropriately. State and federal review process recommended that Mitigation should be started years in advance for NCDOT projects. This lead to the creation of the NC EEP which ultimately absorbed WRP. Sometimes sites that are built by dot are transferred to eep for management.

Target Population for NC Mitigation Pilot Study

- > Mitigation Type Restoration.
- > Wetland Type Riverine or Riparian.
- > Permitted 2002-2006.
- > Built ≥ 4 years ago.
- Deemed "successful" in most recent monitoring year for both hydrology and vegetation.
- > Located in areas where trees were planted.
- ➤ Appropriate Size (≥ 0.10 ha) and width (≥ 20 m) for NWCA methodology.

Successful not closed out as in National Design, not enough sites for 2002-2006 Successful for vegetation – 260 stems per acre at year five monitoring, Hydrology depended on goals of Mitigation Monitoring Plan, ranged from 5-12.5% consecutive days of growing season within 12 inches of surface. Some restoration sites just have hydrology returned, we stayed in areas where vegetation was also planted to be consistent.

-		ion Methods Riverine Restored			
Mitigator	Number of Components	Acres			
In-Lieu Fee (EEP)	42	667			
Mitigation Bank Permittee-	11	541			
Responsible	11	487			
total	64	1695			

Results of Target Population prior to desktop review for success (minimal time for recon)

Mitigation Site Selection

Mitigation Bank and Permittee-Responsible Sites were randomly ordered and first 10 sites were to be surveyed.


≻In-Lieu Fee

Random Survey Design, Generalized Random Tessellation Stratified (GRTS) survey design used.


Study used two approaches for choosing study sites due varying size of target population due to fewer permittee responsible and mitigation

For In-Lieu Fee - GRTS – done by Tony Olsen of the EPA. Sites are spatially balanced state wide. Design is to ensure results are within a 95% confidence interval. GRTS design includes a reverse hierarchical ordering. List of base sites provided (10) and over 100% over sample sites (32). Sites used in provided site order, if a site drops the first oversample is then evaluated and used.


If <10 sites of the mitigation / permittee responsible were deemed unusable then next oversample In-Lieu fee site would be selected. * we did not have more AA in larger sites as in national design.



5 10x10 meter plots were set up along plot placement lines, water quality collected-DO, pH, conductivity, nutrients, sediment/silt clay content, TOC, Soils – Soil chemistry, Soil isotypes, bulk density, soil enzymes, - Hydrology – observable wetland features that affect hydrology – inflow/out flow, impacts -ditching, berms, roads, culverts, etc, evidence –water marks, sediment depotsits, , surface water etc, Vegetation – vegetation cover, structure, height class / dbh for trees, gound cover



Permitee-responsible sites – 6, mitigation bank 8, In lieu fee – 16, Sites dropped for various reasons – Desk top review identified some that were not successful (most common) or were not Riverine, some were not 4 years old, were denied access to one private site.




The ELI study methods were finalized before the National Study Design was finalized. In a number of cases we mimicked methods used in Ohio since the two studies will be compared.

Hydrology – field sheet metrics that looked at whether the design of the site provided / controlled hydrology- NWCA did not collect info on.

WQ – used DWQ lab, so they were unable process Sediment Silt Clay content, Sediment TOC and some of methods different. pH also taken in field along with DO and conductivity.

Soils – Midwest laboratories which was used in the Ohio study. Soil Isotope and sediment enzymes not collected. Chemistry methods and some parameters dropped. Bulk density collected at 15cm middle of profile (100 ml). Second hole dug and 0-30 cm collect – composite (kg needed). We dug pits (auger used in ohio).

Buffer – Same Buffer methods also did LDI for 100m buffer Some preliminary results to be discussed.



Standard AA used at



IMPORTANT NOTE: For buffer **plot** layout, a set max distance is always used. For **BUFFER ZONE** as defined by RAM, the buffer extends 100 meters from the AA perimeter in all directions. Due to this difference in definitions, the Buffer Plots may not lay evenly across the buffer zone, or may lay outside of it in some cases.

80 m circle did not fit in this area, but a wide rectangle of 0.5 hectares did. Short axis is between 40 and 80 meters wide

Notice that the plot placement lines are perpendicular to each other, but need not be along cardinal headings (though teams will quickly figure out that it is easier if they do).

Veg plots are laid out as closely to standard as possible (same as standard in the case of the very wide polygon)


Buffer plot lines are still along cardinal headings

Plot distances for each set of buffer plots needs to be calculated independently. Buffer plots are:


#1 at edge of AA (Slight overlap is acceptable)

- #3 is centered at 135 meters from CENTER
- #2 is halfway between 1 and 3


If buffer plot end up less than 10 meters apart, the short plot lines can be lengthened as necessary



Used the plan sheets to draw. Mason (In Lieu Fee) Component part of larger project. Point generated in random location. This point we had to shift just a little bit, standard 40 m radius survey area. Component that was considered riverine. Keyed as non-tidal freshwater marsh. 2006 site, small trees.




Lloyd (In Lieu Fee), shifted. Did not consider areas that were too narrow.




Lloyd survey results, point moved west. Narrow Polygon survey set up.

Water Quality Field Results							
Calcula	tion	Parameter	In-Lieu Fee	Mitigation Bank	Permittee Responsible		
Sample	Size		9	4	2		
Mir			21.6	85.8	71.6		
Max			395	201.8	2719		
Rang	e	Conductivity μS	373.4	116	2647.4		
Mea	n		139.5	138.6	1395.3		
Medi	in		112	133.4	1395.3		
Mir			0.6	0.4	0.2		
Max			8.1	5.5	6.1		
Rang	e Diss	olved Oxygen mg/L	7.5	5.1	5.9		
Mea	n		4.6	2.725	3.15		
Medi	an		5.3	2.5	3.15		
Mir			4.2	3.75	4.11		
Ma			6.4	6.16	5.39		
Rang	e	рН	2.2	2.41	1.28		
Mea	n		5.7	5.235	4.75		
Medi	an		5.7	5.515	4.75		
Mir			16.4	22.2	18.3		
Ma			29.3	27.4	30.6		
Rang	e	Temp C ^o	12.9	5.2	12.3		
Mea	n		22.2	25.25	24.45		
Medi	in		21.2	25.7	24.45		


Preliminary wq field results presented here. Only really obvious differences were the high levels conductivity at some of the permittee responsible sites that had brackish water.



Hydric characteristics – wet influence-more general all soils. Field indicators matched with specific soil types. – NRCS list that show hydric processes, field indicators are more rigorous detailed explanation of wetland soil condition.



LDI is a land cover analysis (Brown and Vivas) that is applied to a given area (100 m buffer) that incorporates the intensity of the land cover type weighted by the area of that land cover type. The more intense the land use – the higher the LDI value. Some of the permittee responsible sites that were private owned had higher (although probably not significantly higher) when built on-site , e.g. banner elk lowes.



Prelim Veg results similar for 3 types of mitigation. Mean varied from 50-62.

<section-header><list-item><list-item><list-item><list-item><list-item>

USA Ram – read slide, **NC WAM** – Developed by interagency federal and state team from 2003-2008. **ORAM** Also developed by an interagency team for use on Ohio wetlands


NCWA	 					d FW Struc			IS a	and
FWS Status and Trends Vegetation Structure	Bottom Land Hardwood	Headwater Forest	Non-Tidal Freshwater Marsh	Riverine Swamp Forest	Riverine / Riparian	Estuarine Woody Wetland	Non-Riverine Swamp Forest	Pine Flat	Non-Riverine/Riparian	Total
Emergent	1	1	4	1	7	0	1	1	2	9
Shrub/Scrub	4	2	0	5	11	1	1	1	3	14
Forested	2	2	0	2	6	0	0	1	1	7
Total	7	5	4	8	24	1	2	3	6	30

24 of the 30 sites were considered Riverine / Riparian by NCWAM, 6 were not- due to the fact that our database reflected what was in the report and that NCWAM keys wetlands with USGS maps crenulations, at some mitigation sites streams built in flats and not recognized on USGS maps.


NCWAM classifications and FWS Status and Trends lumped by veg structure -Emergent –herbaceous, schrub shrub – woody saplings/shrubs <6m, forested – trees ≥6m





Examples of three different vegetation structured sites, Mitigation Bank Forested Deep Creek (NCWAM – riverine swamp forest), In-Lieu Fee Scrub shrub Floogie (NCWAM – riverine swamp forest), and Emergent Permitee –Responsible Banner Lowes (NCWAM – Non-tidal Freshwater marsh)



24 High, 5 medium and 1 low overall, by mitigator also primarily high with 13 high In lieu fee, 6 high mitigation bank, and 5 high permittee responsible







First three box plots are all the sites by vegetation structure, Next 7 are NCWAM types, For the NCWAM sites, A and B had significant difference with each other but not with A/B

