

Compensatory Stream and Wetland Mitigation: An Evaluation of Regulatory Success

> Tammy Hill – NCDWQ Eric Kulz – NCDWQ Breda Munoz, PhD – RTI John Dorney - NCDWQ

USEPA Wetland Program Development Grant

Grant for three years (2006-2009)

- Three staff positions for 401 compliance (ROs)
 - Assess compliance with conditions in 401 permits
- Two staff positions for mitigation compliance (CO)
 - Assess compliance with 401 permit mitigation requirements



Federal Highway Administration (FHWA) Process Review (1995)

- Process Review Team
 - FHWA, USACE, USFWS, NCDEHNR and NCDOT
- Evaluated mitigation for highway projects
- Selected convenience sample of seven
 - Permits issued 1986-1992
 - Reviewed permits, plans
 - On-site inspections
- Evaluation asked two questions:
 - 1) Is site a jurisdictional wetland?
 - 2) Is site the type of wetland designed?
- > Of five sites reported, only one (20%) was successful



Results of 1995 FHWA Process Review

Site	Target WL Type/ Treatment	Wetland? (Y/N)	<i>Wetland Target Type (Y/N)</i>	Success? Y/N
Sneads Ferry	Marsh/ Restoration	Y	Y	Y
Evans Road	BLH ¹ / Creation	Y	Ν	Ν
Pridgen Flats Bank	Pocosin/ Restoration	Partial	Ν	Ν
US 52 Bypass	BLH ¹ / Rest. & Creat.	Y	NA ²	Ν
US 70A	BLH ¹ / Restoration	Partial	Ν	Ν

¹BLH = Bottomland Hardwood

²The reason for NA under the Wetland Target Type is unknown

Source: FHWA (1995) Process Review






An Evaluation of Wetlands Permitting and Mitigation Practices in NC (Pfeifer & Kaiser, 1995)

- > 59 permits (82 mit. "actions") reviewed
- ➢ Permits issued between 1/91 and 12/93
- ➤ 41 projects visited
- > 20 projects completed, 14 partially completed
- > Same questions asked as previous study
- Also considered target wetland size
- Of 24 projects, only 10 (42%) were successful



Results of Pfeifer & Kaiser Evaluation





Source: Pfeifer and Kaiser (1995)

2006 Implementation Grant Tasks

- Compile and organize mitigation files
- Develop and populate mitigation database
- Develop site inspection forms
- Establish target population for study
 - Projects permitted 1/96 12/06



2006-2007 Implementation Grant Tasks

- > Determine app. sample size (95% conf.)
- Stratify by proportions
 - Mitigation providers
- Select sample sites (random number gen.)
- Determine sites not evaluated
 - Duplicates
 - Not mitigation projects
 - Projects not constructed yet
 - Projects constructed recently (<1-2 yrs. old)





By the Numbers.....

Population \geq 130 wetland sites ► 193 stream sites Sample Size > 98 wetland sites >129 stream sites


After removal of sites not evaluated....

Final Numbers - Wetlands

82 Wetland Sites

> 205 components; >20,000 acres

NC Mitigation Study Sites - Wetlands






Final Numbers - Streams

79 Stream Sites

> 136 components; \approx 600,000 linear ft





"Regulatory" Success

- Problem: Defining "Success"
- Decision: At the time of the site visit, the site was meeting the success criteria approved in the original restoration plan



Overall Success Rates


Mitigation Components (numbers)
➢ Wetlands 74% (70% excluding P)
➢ Streams 75% (74% excluding P)

Mitigation Area or Length (size)
➢ Wetlands 70% (64% excluding P)
➢ Streams 84% (75% excluding P)



Success Rates by Provider

By component counts: No significant difference






Success Rates by Provider

By size, private mitigation had a statistically significantly higher success rate than:


- NCDOT off-site wetland mitigation
- EEP/WRP DBB stream mitigation (only w/ P included)





Success Rates by Physiographic Region


- By component count: No significant differences
- By size: Piedmont streams & Mountain wetlands had lower success rates than other regions





Success Rates by Mitigation Activity


- Preservation most successful (stream & WL)
- Wetlands: no other significant differences
- Streams: Enhancement had a significantly higher success rate than restoration





Success Rates By Age

Streams: No significant differences
 Wetlands: By size, newer projects less successful than older projects





Other Variables

- Project Size: No statistically significant difference in success rates
- Ecosystem Type (Wetlands): No significant difference between riparian, non-riparian, coastal WL
- River Basins/Ecoregions: Sample sizes too small to yield conclusive results



Statistics Summary

- Wetland success not statistically higher than stream success
- Preservation is very successful
- Stream enhancement more successful than stream restoration
- Piedmont stream mitigation less successful than Mtns and Coastal Plain
- No significant difference between mitigation providers, except as noted



Discussion

- Impractical to assume every acre/linear foot of mitigation will be successful
- Wetland mitigation success much improved since 1995 studies
- Stream success lower in Piedmont
 - More bank erosion/structure failure
 - More difficulty establishing woody veg
 - Particularly observed where site excavation required (e.g. "Priority 2" restoration)



Discussion

- Longer monitoring periods likely warranted
- Updated monitoring and success criteria needed
- Greater regulatory oversight/input needed
- Improved recordkeeping and access to data needed



Comments



- Final report has been posted on DWQ Website:
 - http://portal.ncdenr.org/web/wq/swp/ ws/401/certsandpermits/mitigation
- Version of report submitted to Environmental Management for publication in October 2011 (still in review).



Questions??





